


**ROOF FRAMING PLAN NOTES:**

SEE TYPICAL FLOOR FRAMING PLAN FOR ADDITIONAL NOTES



SPAN DIRECTION OF 2" DEEP 20 GAGE FLOOR DECK WITH 3.25" LIGHTWEIGHT CONCRETE TOPPING. REINFORCE WITH WELDED WIRE FABRIC (6 x 6 - W1.4 x W1.4)



NEW 6" DIAMETER STANDARD STEEL PIPE THRU ROOFING




W8x35 COLUMN STOPS AT ROOF FRAMING LEVEL



W8x24 POST STARTS AT ROOF FRAMING LEVEL

NEW STEEL IN CENTER THIRD OF BUILDING TO BE APPROX 3'-0" BELOW EXISTING TOP OF ROOF

ROOF FRAMING BEYOND MECHANICAL ROOM ENCLOSURE TO BE SIMILAR TO TYPICAL FLOOR FRAMING UNLESS NOTED OTHERWISE



**51 BRATTLE**



24 OCT 88

JOB NO. 3111

SK 24

BENJAMIN THOMPSON & ASSOCIATES, INC.

**LeMessurier Consultants**  
CONSULTING ENGINEERS

1033 Massachusetts Avenue  
Cambridge, Massachusetts 02238  
(617) 868-1200

200-1089 ✓