



Notes: Scale of details 8'-10" unless otherwise noted.
 All concrete shall be above concrete 1'-4" min.
 Hangers shall be set in concrete slabs where hung ceilings are called for, and steel beams connected "C" shall be wide flanged shapes unless by Georgia Steel Co.
 All cutting shall be concrete filled steel pipe made by the Lilly Co. unless otherwise noted.
 In detail note with bearing walls shall have blocks laid with cells vertical where steel beams frame into T.C. wall brick bearing plates shall be used where beams rest on T.C. wall and full width of floor shall be concrete unless otherwise noted.
 All slabs to have concrete bars 3/8" dia. unless otherwise noted, all slabs shall be 4" below finish, beams shall be 8" below finish, unless otherwise noted.
 Dowel all slabs to walls with 3/8" dia. 3' o.c.
 All stiffeners to be fitted not welded.

Magill Revised Feb. 14 and plan of Front Entrance steps, added plan and section (W-W) of Paschale entrance to basement level.
 Job No. 120 Date Issued March 17, 1930.
 Sheet No. 102
 Title of Job
 FACULTY CLUB OF HARVARD UNIVERSITY
 15 Prescott Street
 CAMBRIDGE, MASS.
 FIRST-FLOOR FRAMING
 Architects
 Coolidge Shepley Bulfinch & Abbott
 Boston, Mass.